

Service Bulletin

SB 80-6
11-29-79



SUBJECT: HORNS
VEHICLES: 308 GTB (U.S.A. VERSION)

SERIAL NO.

Early production (first 200 vehicles)

REISSUE OF TECHNICAL BULLETIN #301, DATED 3/17/77

CONDITION:

Sound of the horn is too loud inside the passenger compartment.

CAUSE: Location of horn

CORRECTION:

Installation of a new type horn, ("FIAMM TA/U Gemini") and mounting bracket to the center of the upper front frame bar. (See illustration.)

PARTS

INFORMATION:

The part numbers for the new horn and mounting bracket are:

<u>Description</u>	<u>Part No.</u>
Horn (FIAMM TA/U Gemini)	60309903
Mounting bracket	60309804

